



# **Sample Preparation Laboratory (SPL) Overview-Feb. 2024**

B. D. Miller, E. Flynn, J. Trent, S. Moore, C. Judge

# What is SPL and Why is it Needed?

- SPL's mission will be to support characterization of engineering and microstructural scale reactor structural materials
- Post-irradiation examination
- Hazcat 3 facility
- Sample preparation
- Mechanical properties testing
- Microstructural analysis
- No loose alpha bearing materials
- Office space
- Machine shop (Future)




SPL-August 2023

# SPL Location and other Primary PIE Capabilities at MFC

- HFEF handles full sized fueled experiments (Engineering Scale)
- IMCL provides high end microscopy, thermal testing, and small-scale mechanical testing of irradiated materials including sample preparation of commercial fuel pellet sized experiments
  - Micro to atomic scale
- **SPL handles alpha clean structural experiments for microstructural characterization**
  - **Engineering through sub-micron level**
- HFEF, IMCL, and SPL are broadly available to the nuclear research community through the Nuclear Science User Facilities, University partnerships, DOE programs, and Strategic Partnership programs



MFC





# SPL Design Parameters and Cost

- Approx. 4088 sq. meters. (3 stories)
  - Braced frame structural steel with 0.3 meter. solid, grouted, reinforced concrete masonry unit (CMU) exterior walls
  - Seismic Design Category 2, Limit State B
- Divided into office space and laboratory space
  - User facility building designed for easy access by visiting researchers
  - 762 sq. m office space, 3100 sq. m laboratory space
  - Office space provided on all three floors
- 1<sup>st</sup> floor: Shielded sample preparation line and instrument enclosures
- 2<sup>nd</sup> floor: Hoods, gloveboxes, transfer cell of the shielded sample preparation line
- 3<sup>rd</sup> floor: Manipulator repair area, personnel decontamination room, and ventilation
- \$166 Million US Dollars






# Time Frame

- Currently under construction
  - Started in FY2020
- Status of Feb. 2024
  - Main shell of building in place
  - Hot cell is poured
  - Shielded enclosure walls in place
  - Office spaces completed
  - Working on HVAC system and finishing aspects of the facility
- Expected completion of construction in Oct. 2024
- Perform MSA/ORR demonstrations through FY2025
  - MSA-Management Safety Assessment
  - ORR-Operational Readiness Review
- Fully operation at some point in FY2026



# SPL 1<sup>st</sup> Floor Layout


- Office Space
- **Shielded Instrument Enclosures with separate control rooms**
- **Sample Preparation Cells**
  - Sizing, polishing, and grinding
  - Decontamination
  - Sample storage
- **Mechanical Properties Test Cell (MPTC)**
- Truck Bay – Cask Receiving
- Future space






# Hot Cell Layout and Properties

- Multi-room cell for various activities
  - Cask docking cave
  - Transfer cell
  - Sizing, grinding, and polishing cell
  - Decontamination cell
  - Storage cell
  - Mechanical properties test cell (Not Shown) (MPTC)
- Cell has 1.2 m. thick concrete wall
  - 0.91 m high density concrete ceilings



# Material Transfer Cell (2<sup>nd</sup> floor)

- 2 sets of manipulators
- Main purpose of cell is to load/unload casks and to decontaminate materials
- Tooldrop system
- Crane to help unload experiments and to transfer experiments
- Glovebox attached on backside of cell
  - Contamination measurements
- Shielded container mate up station
- Access door to the cell for decontamination and material introduction/removal
- Plug to shield cell from sources in SPG cell





# Cask Docking Cave


- Truck lock to unload casks using a rail system and cask cart
- Accept a variety of casks using adapter plates
  - BEA Research Reactor (BRR) Cask, primary cask for transfer between ATR and SPL
  - HFEF-5 waste cask
  - Shielded 55-gal drum (208 liter)
  - GE-100
  - Others with correct mate up systems



Cask Docking Cave Minus Cart

# Sizing, Grinding, and Polishing Cell-SPG Cell



- 2 sets of manipulators
- Receive material from the Material Transfer Cell (2<sup>nd</sup> Floor)
- Storage locations for material
- Polisher/grinder
- Sectioning by saws and other methods
- Electro Discharge Machine (EDM)
  - Access door to the EDM if needed
- Tooldrop system
  - Introduction of tools and supplies
- Crain to support lifting samples and equipment
  - Shared with the decontamination cell via sliding door



Conceptual design of the SPG Cell

# Electro Discharge Machining (EDM)

- 4 Axis machine EDM thru Viteris
- Self spoiling
- Mill capabilities
- Multiple tooling capabilities
- Will be remotized as much as possible
- Removable from cell for complex maintenance via rail system and adjacent access door




Conceptual Designs of the EDM



# Decontamination Cell

- 1 set of manipulators
- Primary purpose is to decontaminate samples
  - Ultrasonic cleaners
- Optical microscopy
  - Sample identification and polish conditions
- ~~Sputter coater (Moved to Enclosure)~~
  - ~~Electrically grounding of samples~~
- Hatch above for access to the cell
  - Removed by crane on second floor
- Tooldrop system
- Transfer capability to glovebox on backside of cell

Decontamination Cell




# Sample Storage Cell

- 1 set of manipulators
- Capability to store 1,800 standard samples with 100 mechanical property test samples in below table storage
- Crain to help lift sample storage containers from floor storage
- Tooldrop system
- Pneumatic rabbit system for transfer to various locations in laboratory
  - 3 shielded enclosures
  - MPTC
  - 2<sup>nd</sup> floor glovebox line
- Ceiling shielded plug that is removal by 2<sup>nd</sup> floor crane for access to cell




Pneumatic Transfer Station




Sample storage cell

# Mechanical Properties Testing Cell (MPTC)

- 0.91m thick concrete side walls with 0.6m high density concrete ceiling
  - Rated for 10 Ci of  $\text{Co}^{60}$  (370 billion Bq)
- Tooldrop system
- Rabbit system from sample storage cell
- **Four UR10E robots to support instrument loading activities**
- U tubes for instrument connections into the floor
- Instruments:
  - **Instron load frame**
  - **Charpy impact tester**
  - **Hardness tester**
  - **Annealing furnace**
  - **Optical microscopy**
  - **Welder**
- **Access Door for entry into cell**



Planned Layout of MPTC




View of inside the MPTC





# Shielded Instrument Cells

- 3 shielded enclosures for instruments
- 21 cm thick steel walls
  - Rated for 0.25 Ci of Co<sup>60</sup> (9.25 billion Bq)
- One future pad/area designated for future shielded enclosure
- All 4 pads serviced by rabbit system
- Planned instruments for cells
  - X-ray diffraction
  - X-ray photoelectron spectroscopy
  - Focused Ion Beam Spectroscopy
- Instruments operated in outside room via U-tube connection
- All instruments will have capability to be loaded with robots
- All support equipment for instruments will be on 2<sup>nd</sup> floor
- Access doors to perform low level work, instrument setup, and maintenance




# SPL 2<sup>nd</sup> Floor Layout

- Office Space
- Instrument Support Equipment
- Material Transfer Cell
- Glovebox/Fume Hoods Line
- Support equipment rooms for instrument rooms on 1<sup>st</sup> floor
- Space for expansion
  - Robotics development area
  - Machine shop (future)



# Glovebox/Hood Line

- Large glovebox for highly contaminated materials
  - Glovebox has shielded storage locations
- 6 fume hoods with connection to the glovebox to two of the hoods
  - 5 contaminated hoods for various activities
  - 1 larger non-radiological hood for chemical work



Side view of glovebox line



Glovebox design




# SPL 3<sup>rd</sup> Floor Layout


- Office Space
- Air Cleaning Equipment (HEPA)
- Manipulator Repair Area (MRA)
- Mechanical Equipment
- Tool Room
- Personnel Decontamination Room
- Limited extra space for future expansion



MRA




MRA



# Application of Robotic Technology in SPL

- Robots will be utilized in various locations in SPL for activates
- MPTC-Four UR10E Robots
- Instrument cells will utilize a UR5E arm to perform loading activities
- All robots will be programable for repetitive actions and can be operated freely with the use of cameras attached to the robot
- Multiple cameras in areas to support use of the robots



Dual Arm Robot Teleoperated System



# Application of Robotic Technology in SPL



UR5E robot and instrument set up



Loading  $\frac{1}{2}$  compact tension specimen in Instron mockup via two UR10E robots





# Questions!