

Laboratory for Operations and Testing in the United States (LOTUS)

NRIC Test Bed

NRIC-LOTUS Project Team – Aaron Balsmeier, Jacob Rymer, Scott Reynolds, and Scott Smith 04/23/2024

Z NRIC-LOTUS Test Bed





NRIC-LOTUS Information

Location: INL Materials and Fuels Complex (MFC); Zero Power Physics Reactor (ZPPR) Facility

Purpose: Provides infrastructure to support DOE authorized experiments requiring a Hazards Category 2 facility with an elevated security posture

ZPPR Facility Footprint

LOTUS Facility Footprint






Z NRIC-LOTUS Design Details

Advanced Experimental Reactors

- Fuels designs with Highly Enriched Uranium
- Cell Heat Removal (2) redundant HVAC packages 50kW_{th}
- Reactor Heat Removal Design only Min: 25 kW_{th}; Max: 400 kW_{th}
- Argon Cover Gas 2 scfm, 90 psig (SS), 15 scfm, 90 psig (1 hr max)
- In Cell Equipment Power
 - Normal 480VAC, 450A, 3 phase
 - Auxiliary 208VAC, 160A, 3 phase
- Cell Provides Radiological Confinement
- Cell Geometry 30ft usable inner diameter; 16ft 11in (bottom of crane hook); Recessed pit area
- Entry Tunnel 13ft x 13ft clear pathway
- Polar Crane Capacity 5 tons






NRIC-LOTUS Project Schedule

Schedule

- Conceptual design completed 12/2021
- CD-0 (Mission Need) approved 3/2022
 - Tailored Approach Changed from CD-1/2/3a 1/2023
- CD-1 approved 6/2023
- Awarded prelim/final design 6/2023
- Preliminary design review completed 1/2024
- Technical independent project review (TIPR) completed 3/2024
- Final design complete 4Q/FY24
- Submit PDSA 4Q/FY24
- Submit CD-2/3 2Q/FY25
- Construction finish forecast* 2Q/FY27
- Operational readiness forecast**– FY27/FY28

^{**} Start of operational readiness to be influenced by completion of construction. Operational readiness anticipated to require ~9 months. Opportunity to initiate first reactor experiment install coincident to operational readiness activities.





^{*} To be informed based on construction bids

NRIC-LOTUS Project Funding

Major Project Area	FY22 (A)	FY23 (A)	FY24	FY25	FY26	Total	Notes
Total Estimated Costs – Capital Account		\$22.25M	\$32.00M	\$18.75M		\$73.00M	Includes TEC management reserve
Other Project Costs – Capital Account	\$6.56M	-\$1.85M	\$2.90M	\$9.00M	\$8.59M	\$22.20M	Includes OPC management reserve
Total LICP Budget*						\$98.20M	

LICP: Line-Item Capital Project



NRIC-LOTUS Next Steps

- Complete Final Design
- Update Safety Design Strategy
- Complete Preliminary Documented Safety Analysis
- Update project documentation to support CD-2/3
- Submit Documentation for CD-2/3
- Establish Performance Baseline and award construction subcontract





NRIC-LOTUS Digital Model











Molten Chloride Reactor Experiment (MCRE) Project Update

MCRE lays the foundation for commercial MCFR deployment

Molten Chloride Reactor Experiment

- Advanced Reactor Demonstration (ARD) Risk Reduction Award
- Collaboration led by Southern Company
- TerraPower responsible for reactor design and fabrication
- INL responsible for fuel salt production, reactor installation, operation, and post-operations decommissioning
- INL host site, NRIC-LOTUS reactor test bed
- Critical operation in 2027


















Objectives

- 1. Safely achieve criticality
- 2. Determine reactor physics and kinetic parameters to reduce uncertainty and gather data
- 3. Demonstrate fuel handling strategy for chloride fuel salt
- 4. Initiate industrial supply chain for molten salt components
- 5. Collect data for licensing framework

MCRE is the second large demonstration along the MCFR deployment path, building upon DOE's ARC'15 investment in the Integrated Effects Test (IET)






Molten Chloride Fast Reactor (MCFR)

Liquid Fuel Salt

- High operating temperature improves power conversion efficiency and enables valuable industrial applications
- Low pressure system removes need for thick, expensive vessel walls
- Flowing fuel eliminates need for refueling outages and provides load following reactivity control

Fast Neutron Spectrum

- Core can tolerate fission products and achieve high burnup
- Reactor breeds new fuel and utilizes that fuel directly without need for a reprocessing plant
- Destroys longest-lived nuclear waste isotopes, reducing amount of waste and shortening the hazardous lifetime





INL MCRE team has developed an elegant process for fuel salt synthesis



INL MCRE Project Status

Recent Accomplishments

- Fuel Salt Synthesis Line Final Design activities complete
- Initial full-scale fuel salt synthesis demonstration (9kg depleted uranium) complete
- Completed world-first measurement of oxygen concentration in fuel salt
 - Results show INL synthesized fuel salt outperforms technical specification
- Reviews completed for 14 of 17 total MCRE systems in preparation for plant level Preliminary Design Review in May

FY24 Deliverables

- Begin installation of Fuel Salt Synthesis Line
- Fabricate first-article set of Fuel Salt Containers
- Complete off-normal oxygen and moisture ingress experiments with fuel salt
- Perform initial salt spill experiments
- Complete Conceptual Design of Irradiated Salt Containers
- Award Design/Build RFP for Fuel Handling Glovebox (FHG)




TerraPower MCRE Project Status

Recent Accomplishments

- 90%+ of MCRE equipment in plant general arrangement
- In contract (or able to extend contract) for <u>all long lead equipment</u> for Mockup
- Full cycle of RIPB safety evaluation completed and Conceptual Safety Design Report (CSDR) submitted
- Completed ³⁵Cl nuclear data measurements and reactor core optimization enabling significant reduction of MCRE fuel volume
- Mockup site preparation underway and initial hardware delivered
 - 30,000 lbs of MgO reflector bricks and RXE upper and lower loop

FY24 Deliverables

- Complete MCRE Plant Preliminary Design Review
- Award remaining Mockup procurements
- Begin construction of Mockup and confirm engineering design
- Develop operational procedures for Mockup and prepare for salt operations



Achieving the INL Vision, to change the world's energy future, requires participation from technology developers and end users

- Challenges facing the grid and reactor developers today
- Anticipated changes and strategic considerations
- Timing and magnitude of future power generation needs
- Planning processes and parameters that influence new technology adoption
- Synergies with existing collaborations and partnerships






















Questions?

James King james.king@inl.gov





This material is partially based upon work supported by the Department of Energy under Award Number DE-NE0009045. This content was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.



DOME Test Bed Ecosystem

Troy P. Burnett, P.E.

04/23/2024

Z DOME Panel Agenda

- DOME Ecosystem Troy Burnett
- DOME Construction Update Scott Smith/Brandon Hill
- Supplemental Shielding Design Chance Price/ Kyle Reno (Enercon)
- Polar Crane Status Update Chance Price
- Fuel Storage at INL Todd Sherman
- DOME User Guide Marvin Fielding
- FEEED Overview and Update –Troy Burnett
 - Westinghouse Erin Orga
 - USNC Wes Deason
 - Radiant Elliott Korb



Z DOME Test Bed Ecosystem

- DOME Ecosystem
 - Facility
 - Equipment and Infrastructure
 - Process and Procedures
 - Developers
- Current Progress and Status Updates
- Path Forward






Z DOME Facility

- Facility Specifications
 - Hazard Category 2 facility
 - Provides safety class confinement
 - Large floor space for reactor experiments
 - ~ 65' ft diameter
 - ~ 46 ft height to crane
 - Hatch Opening
 - ~15' wide
 - ~17' tall
 - Penetrations
 - Small penetrations for process
 - Large Penetrations for primary reactor cooling
 - Control Room
 - Space for developer control room in connecting building or pad outside








Z DOME Facility Continued

- Operational Features
 - Allows capacities up to 20MW thermal
 - High-Assay Low-Enriched Uranium (HALEU) TRISO fuels
 - 300kW of environmental cooling
 - Scalable to 500kW
 - 480V/400Amp electrical service
 - Exterior pad for primary reactor cooling and reactor support equipment
 - Shipping Container Capacity: ISO-668 standard





Equipment and Infrustructure


- Existing Infrustructure
 - Utility access for compressed air, deionized water.
 - Access to equipment: forklift, crane.
 - Post Irradiation Examination
 - Fire Suppression
 - Security
- Planned Infrustructure
 - 75-ton polar crane
 - Reactor handling system
 - Supplemental Shielding






E&I Continued

- Fuel Storage
- Rad Waste management
- Rigging equipment
- Decontamination equipment
- Reactor Supplemental Shielding
- Transportation equipment
- Remotely operated equipment





Process and Procedures



Z Process and Procedures Cont.


- User Guide Revision
- Operations Training plan
- Environmental Assessment for testing advanced reactors in the DOME
 - Plant Parameter Envelope
 - May eliminate the need for a full Environmental Assessment for each reactor






Developer Engagement

- Front End Engineering and Experiment Design (FEEED)
 - Awarded 3 FEEED applicants in 2023
 - Radiant
 - USNC
 - Westinghouse
- Progressing toward Phase 2, Detailed Design and Long Lead Procurement









Z Look Ahead

- Program Development
 - Environmental Assessment
 - Update DOME User Guide
 - Fuel Cycle Plan
- Equipment and Infrustructure
 - Initiate Polar Crane Repair
 - Supplemental Shielding
 - Finalize Design
 - Begin Procurement
 - Reactor Handling System
 - Develop Fueling/Defueling
 Strategy







Summary

- DOME Facility Construction
 - Full Construction Release granted to Estech October 2024
 - Scheduled to complete late FY 2025
- Test Bed Equipment and Infrustructure
 - Numerous tasks underway
 - Plan is in place to support reactor installation in 2026
- Process and Procedures for Testing
 - Continue to define the program in more detail
 - Continued improvement
- Developer Engagement
 - Continue progressing through FEEED with 3 developers
 - Looking to progress to Detailed Engineering and Long Lead Procurement







DOME Construction

Scott Smith Brandon Hill

04/23/2024

Accomplishments

- Construction Subcontract award to ESTECH Aug 23
- Partial Notice to Proceed for ESTECH mobilization Sept 23
- Final NTP for full construction activities Oct 23
- Quality Inspection Support awarded to ATLAS Feb 24
- Request for Proposal to award a Commissioning Agent subcontract issued - Apr 24
- Construction activities projected completion Jun 25



Accomplishments – Schedule and Cost Improvements

The NRIC Team continually evaluates methods to improve schedule and cost:

- Construction specification allows the QL3 subcontractor to order NQA-1 components for future commercial grade dedication by BEA.
- Epoxy Irradiation experiment to allow for more efficient and cheaper installation of the DOME Hatch.
- GFE strategy:
 - Allowed the Construction award to be QL3 vs QL1
 - Long lead procurements prior to subcontract award



Government Furnished Equipment

- The Project employed a strategy to provide GFE to the Construction Subcontractor resulting in Project cost and schedule improvement.
 - NRIC procurement of NQA-1 GFE allowed the Construction Subcontract to be awarded as QL3 vs QL1.
 - Long lead procurements prior to subcontract award resulting significant schedule improvement up to greater than 1 year.
- GFE Received as of Apr 24 include:
 - Pressure and temperature detectors, Swagelok valves, HEPA filters, medium voltage transformer, and low voltage switchboard.



Government Furnished Equipment

Expected schedule for receipt of rest of GFE includes:

- Radiation monitor Jul 24 (Mirion).
- Power and I&C Penetration assembly Aug 24 (Mirion).
- Hatch and Utility Penetration Assembly Aug 24 (Petersen).
- Containment Isolation Valves (air exhaust, and water) Aug 24 (Enertech).
- Plant air Spring 2025 (Valcor)
- Personnel door Jun 24 (Walz & Krenzer).
- AHU expansion tank May 24 (Gritton).
- Safety Class Duct Bank June 2024 (TRENWA).
- Medium Voltage Sectionalizer Summer 2025 (D&S). A mitigation plan to install a temporary sectionalizer is in place to ensure this does not impact schedule.



Risk Management

Significant project risks to cost and schedule include the following.

- Delay in receipt of Government Furnished Equipment due to supply chain issues or Contracting/QA requirements.
- Additional design improvements based on unexpected field conditions.
- Potential scope change to include crane repair or thermal sleeve installation in the construction subcontract.



Z Schedule – Major Milestones

- April 2024 Award Commissioning Agent Subcontract
- June 2025 Complete Construction
- October 2025 DOE Approve Documented Safety Analysis
- March 2026 Complete Testing
- March 2026 Complete Turnover and Operational Readiness
- April 2026 Complete Project



Z Schedule and Cost Performance

SPI and CPI Data as of March 2024:

- **CPI 1.1** slightly under budget due to late invoicing by the construction subcontractor for procured items than was planned. This CPI trend is expected to trend towards 1.0 as these items are ordered.
- **SPI 0.8** currently behind schedule due to finding unexpected underground utilities and weather delays. Schedule recovery is trending towards 1.0 as the project continually identifies more efficient ways to perform the work.



DOME Construction Flythrough


The video includes a 3D model projection of the DOME facility final design including recent photos of current construction progress.

VIDEO


https://confluence.de.inl.gov/download/attachments/1073 80978/2024-02-13%20NRIC%20Video%202.mp4?api=v2



Z Additional Photos

























DOME Reactor Supplemental Shielding (RSS)

Chance Price

04/23/2024

Z DOME RSS

- A radiation shielding system is needed to protect personnel and equipment from harsh neutron and photon fluxes during:
 - Reactor operations
 - Post shut down operations
 - Disassembly
 - Decommissioning
- Examples of RSS driving requirements
 - Radiological Controls
 - Operating dose rate: the dose rate during normal reactor operations shall be <0.5 mrem/hr at the exterior wall
 of DOME containment
 - Outdoor radiation limit: shielding shall provide the dose to a facility worker outside of DOME to <0.05 mrem/hr at 50 ft from the exterior wall of the DOME
 - Temperature
 - Reactors may have operating temperatures up to 800C
 - The RSS shall be capable of removing up to 100 KW of heat during normal operating conditions
 - the concrete structure has an upper temperature limit of 100°C





RSS Background


- 2022
 - December developed the initial conceptual design (based on a modular configuration) – our initial cost estimate >\$30M



- June INL revised the RSS requirements from small modular configuration to being removable
- September developed an updated conceptual design cost estimate \$10-12M
- December Awarded RSS Preliminary Design Subcontract to Enercon
- 2024
 - February Enercon presented the trade study results (alternate materials, changes to the design/configuration, and high-level cost impacts)
 - Including 3 design options
 - Option 1 with water tank and no natural convection
 - Option 2 with water tank and natural convection
 - Option 3 with no water tank and natural convection
 - March Enercon delivered 60% Preliminary Design









DOME RSS

- Next Steps
 - July Complete Preliminary Design
 - August Initiate Final Design
- Why NRIC will provide the RSS
 - DOME has 30+ years service life with many anticipated advanced reactor tests
 - DOME is above ground with very little inherent shielding
 - Shielding solution is an over constrained challenge
 - Competing structural, radiological and thermal requirements
 - Must interface with the DOME Containment and Heat Removal Systems
 - Very large and expensive
 - NRIC/INL are best positioned to develop the design
 - HTGR reactors have very high neutron and photon flux
 - No water as a coolant
 - Intended to be mobile (no concrete structure around them)
 - DOME's primary purpose is to test advanced reactors rather than shielding







Reactor Supplemental Shielding For the NRIC DOME Test Bed

ENERCON Presentation

Executive Summary


Tuesday, 2/13/2024



Excellence—Every project. Every day.



Agenda



- Objective
- Reactor Supplemental Shielding Design
 - Shielding Requirements
 - Layout
 - Materials
 - Thermal Analysis
- Open Discussion




Objective

Provide an overview of the reactor supplemental shielding being developed for the DOME test bed.

The RSS provides the radiation shielding necessary to keep dose requirements within limits when the test reactors are at full power as well as after shutdown conditions.

The RSS within the EBR-II containment






Shielding Design

Shielding keeps dose below these levels:


- 0.05 mrem/hr 50' from exterior wall of DOME
- 5 mrem/hr at the exterior wall when operating
- 30 cm from components 90-days post shutdown 0.5 mrem/hr outside the shield and 5 mrem/hr inside the shielding enclosure
- ~7' thick concrete or 4.5' concrete + 2.5' of water is needed to keep radiation levels within the above limits.






RSS Layout







Equipment Entry/Removal Point

Modularized RSS Design to Facilitate Installation and Removal within the DOME

Space for reactor to be located within RSS



RSS Materials

Various materials have been considered for use in shielding the reactor. In addition to the shielding capability, the following characteristics are considered

- Activation (will the materials become radioactive after exposure to radiation)
 - Activation drove the selection of aluminum over steel for the water tank
- Cost
 - Concrete is an excellent radiation shield and relatively low-cost material, so it has been used heavily for the shield design
- Weight/Space Limitations
 - These factors have been able to be accommodated without requiring the use of more exotic, expensive materials



Thermal Design/RSS Cooling

The RSS is designed to accommodate developer microreactors that output ~10 MW of thermal power during normal, full-power operation.

Normal Operation:


- 99% of the heat is removed by the primary fluid during normal operation
- The remaining heat (1% or up to 100 kW) is removed by active cooling of the water tank through a chilled water system.

Post-accident/Shutdown:


- If active cooling systems are lost, the RSS must accommodate the decay heat coming from the reactor for a
 period of three days. This decay heat is initially ~7% of the reactor power (up to ~700 kW) and must be
 passively cooled.
- The water tank is sized to hold enough thermal mass for the three-day accident period to protect the surrounding materials from exceeding their temperature limits.



Thermal Design/RSS Cooling



Steady-state concrete temperatures from conceptual design



Steady-state concrete temperatures from preliminary design

The goal of the thermal design of the RSS is to protect materials from experiencing temperature above their limit.

Aluminum plates added under insulation on floor to help spread heat toward the water tank away from floor. These resolved the overtemperature issue on floor concrete and brought max concrete temperature <100C



Summary

- The DOME test best will enable developers to gain valuable operating time and test data on their designs at reduced cost and using the world-class capabilities of the US National Lab System.
- Three microreactors are currently planned to be tested at DOME.
 - Radiant (Kaleidos)
 - Ultra Safe Nuclear Corporation (Pylon)
 - Westinghouse (eVinci)
 - We expect a lot more over the course of 30-40 year life of DOME
- DOME RSS Preliminary Design Efforts are underway!



Q & A

Questions/Open Discussion



DOME Polar Crane


Chance Price

04/23/2024

Background

- 2015
 - The DOME polar crane was being prepared for explosive demolition
- 2018-2019
 - Budgetary planning \$10-12M
 - INL cost estimates to fix was \$12M
 - Estimates were based on a similar project in HFEF
 - Decision was made to explore other options
- 2022-early 2023
 - Explored Gantry Crane Option
 - Space constraints
 - Flexibility constraints
 - Height constraints
 - Operational impacts to timelines
- Late 2023
 - Contracted with American Crane to perform a detailed inspection report that could be used to elicit an accurate repair estimate.
- 2024
 - Requested vendor budgetary estimates for crane repair
 - Received estimates of \$4.5 to 5.5M from 2 vendors
 - At this price point, the polar crane repair is competitive with a gantry crane and provides significantly more flexibility







Z DOME Polar Crane


- 2024
 - Completed trade study for polar crane/gantry crane

Comparison of Crane Options for the DOME Facility


Function	Scoring (1)					
	Polar (2)		Free Standing Bridge		Mobile	Forklift
	NOG-1	CMAA Spec 70	NOG-1	CMAA Spec 70	Mobile	FOIKIII
Lift Capacity	5 (75 to 140 tons)	5 (75 to 140 tons)	5	5	2 (6.3 to 19.7 tons)	2 (25 tons)
Lift Height	5 (38.5 ft)	5 (38.5 ft)	3 (34.8 ft)	3 (34.8 ft)	3 (36 ft)	1 (10.25 ft)
Lift Coverage (**see figures**)	5	5	2	2	2	2
Lift Velocity (3)	5 (1.7 in/min)	5 (1.7 in/min)	5	5	3	1
Footprint (**see figures**)	5	5	3	3	1	1
Single Failure Proof	5	0	5	0	0	0
Efficiency (4)	5	5	2	2	2	2
Capital Cost	\$5.5M	\$3M	\$5M	No data	\$0.5M	\$0.5M

Notes

- Score of 0 to 1: least desirable or does not fulfill needs.
 Score of 2 to 3: could fulfill needs if accommodations are made or additional design restrictions are made.
 Score of 4 to 5: most desirable. Meets or exceeds needs.
- 2. The polar crane values in this table are associated with main hoist. The auxiliary hoist of the polar crane can lift smaller loads (5 tons) to higher elevations (44 ft).
- 3. Slow and controlled lift velocity is important for the precise placement of heavy objects.
- 4. Quantity of operations needed to complete reactor experiment setup and teardown.
- Next Steps
 - Develop the DOME polar crane specification
 - Issue DOME polar crane repair subcontract



<u>Forklift</u> <u>Mobile Crane</u>



Free Standing Bridge Crane

Polar Crane







Fuel Storage Requirements

Todd Sherman

04/23/2024

Fuel Storage Progress

- 2023
 - No fuel storage plan had been developed

- 2024
 - The shipping and receiving requirements are understood
 - A storage location has been selected and designated
 - The storage limitations are known and incorporated
 - The INL coordination and approval groups have been determined




Shipping and Receiving

- Fuel composition, enrichment, fuel quantity per container, number of containers
- DOT certified containers
- DOT-NRC Certificate of Compliance
 - Container specific criticality safety index
- INL Safeguards witnesses the packaging and places tamper indication devices
- Packaging INL is not responsible for packaging
 - · packaging should be compatible with a standard forklift for unloading and handling
 - Disposition of shipping packaging (a.k.a. overpack) is required
- Cooperative Research and Development Agreement (CRADA) and Project Task Statement (PTS)



CPP-651

- Building CPP-651 is an approve unirradiated fuel storage facility
- The South Vault is approved for new fuel storage
 - Areas 1, 2, & 3 are designated for the NRIC microreactor fuel
- Facility limitations
 - Facility aggregate Criticality Safety Index (CSI)
 - Available floor space





Storage

- Storage Plan and Schedule
- Container certification expiration is typically 12 months.
 - If the certification expires then repacking the fuel is required
- Repacking is highly discouraged
 - preparation and approval process is >12 months
- Shipping empty containers
 - Storage plan must include shipping the empty fuel containers to a predetermine recipient



Coordination and Approvals

- NRIC contract and planning
- Material Security Consolidation Facility (CPP-651)
- INL Safeguards
- INL Packaging and Transportation
- Fresh fuel (i.e., prefabrication) would require additional approvals and planning
- Early coordination is vital for success







DOME Reactor Testing User Guide


(Demonstration of Microreactor Experiments)

Marvin W. Fielding, P.E., PMP - Program Manager, NRIC

4/23/2024

Z Agenda

- DOME User Guide Development
- DOME User Guide Focus
- User Engagement Lifecycle for DOME
- Phase 1 Front End Engineering and Experiment Design (FEEED)
- Phase 2 Detailed Design and Long Lead Procurement
- Phase 3 Fabrication, Training, and Delivery
- Phase 4 Installation and Testing
- Phase 5 Removal and Disposal
- Next steps





Z DOME User Guide Development

Feb

- 2022 completed the "Concept of Operations (ConOps)" for MFC and DOE review
- Name changed from "ConOps" to "User Guide"
- Draft User Guide to U.S. Department of Energy (DOE) for comment
- Received DOE comments Aug '23

Sép '23

- Updated DOME User Guide based on final design
- · Received DOE comments Dec '23
- Scheduling
- · Non-technical topics subject to change
- Received input from developers

FY24

- Focused user guide on technical processes
- · Document FEEED lessons learned
- · Mature and document design, testing, and removal phases




Z DOME User Guide Focus

- Provide end-to-end technical requirements for testing in DOME
- Identify DOME facilities, equipment, and capabilities
- Identify applicable standards and documents





Advanced Reactor Testing in DOME



ORR: Operational Readiness Review

SDS: Safety Design Strategy

SME: Subject Matter Expert

PDSA: Preliminary Design Safety Analysis

2: DOE approval required for only safety-

Draft date: 3/27/2024

significant procurements

3: All procurements can proceed

76

NRIC Activity/Milestone

DOE Activity/Milestone

Requires DOE Approval

DSA: Documented Safety Analysis

FEEED: Front-End Engineering and Experiment Design

PSDR: Preliminary Safety and Design Results

UUT: Unit Under Test


Phase 1 - FEEED

Front-End Engineering and Experiment Design

Key Activities

- Conceptual design and Conceptual Design Review
- Develop working documents
- Conceptual experiment design

- User Program Plan
- Class 4 Cost Estimate
- Conceptual Test Plan
- Safety Design Strategy (SDS)
- Conceptual Safety Design Report (CSDR)






Phase 2 - Detailed Design and Long Lead Procurement

Key Activities

- Preliminary Design and Preliminary Design Review
- Final Design and Final Design Review (90% design completion, required for Preliminary Documented Safety Analysis [PDSA])
- Finalize supplemental National Environmental Policy Act (NEPA) information and DOME Environmental Analysis (EA) comparison
- Progress Nuclear Safety documentation for PDSA
- Initial confirmatory reactor analysis
- Begin long lead procurement and manufacturing

- Confirmation of reactor design complying with DOME EA Plant Parameter Envelope (PPE)
- PDSA submittal






Phase 3 – Fabrication, Training, and Delivery

Key Activities

- Procurement
- Unit fabrication and assembly
- Document as-built design
- Initial Operator Training
- Idaho National Laboratory (INL) witness fabrication and assembly

- Unit delivery
- Operator qualification





Phase 4 – Installation and Testing

Key Activities

- Unit Under Test Delivery (UUT)
- Unit installation
- Operational Readiness Reviews (ORR)
- Test campaign/Data collection

- Documented Safety Analysis (DSA)/Safety Analysis Report (SAR)
- Test Data





Phase 5 Removal and Disposal

Key Activities

- Shutdown and cooling
- Reactor removal
- Transport
- Interim Storage
- Defueling
- Disposal

Key Deliverables

DOME ready for next test





DOME User Guide Next Steps

May '24

- NRIC review of revised User Guide
- NRIC National Technical Director review of revised User Guide

Jun '24

Address and Incorporate review comments

Aug '24

- INL reviews of User Guide revision
- Submit updated User Guide 9/15/24







DOME Front End Engineering Experiment and Design

FEEED

Troy P. Burnett, P.E.

04/2024


Z FEED Overview

- Explore the FEEED Process
 - Key Activities
 - Key Deliverables
- Provide an update on FEEED Progress
 - Radiant
 - USNC
 - Westinghouse



Z DOME Test Bed Program

- Developing a new process
- Simultaneously with developers working through the process
- There are a lot of "Known Unknowns"
- Process, procedures,.... Being developed as we go
- Thank you for helping navigate
 - Radiant
 - USNC
 - Westinghouse






FEEED Key Activities and Deliverables

Key Activities

- Program Planning
- Total Project Cost Estimate
- Conceptual Design
- Experiment Design

• <u>Deliverables</u>

- Safety Design Strategy
- Experiment Design Outline
- Conceptual Design Review
- Conceptual Safety Design Report





Z FY 23/24 FEED Process

- Expression of Interest (EOI) advertised in June
 - Received seven expressions of interest
- RFP solicited in July
 - Received five proposals
- Awarded three 80/20 cost share contracts in Fall of 2023
 - Radiant
 - USNC
 - Westinghouse



Z FY24 FEED Work

- Safety Design Strategy
 - Westinghouse received DOE acceptance December 2023
 - Radiant received approval March 2024
 - USNC working on submittal later this year
- Held in person design reviews
 - Westinghouse
 - Radiant
- Strategic Planning
- Consultation and Collaboration
 - Ongoing document and design reviews
 - Fuel cycle planning
 - Fuel Specification
 - Fuel fabrication



FY24 FEED Work Continued

- Conceptual Safety Design Report
 - Radiant
 - Completed review
 - Working on submittal
 - USNC
 - Developing design and documentation
- Preliminary Safety Design Report
 - Westinghouse
 - Completed review in February
 - Comments incorporated
 - Submitted to INL for review and submittal 4/12



FY 23/24 FEEED Status Updates

- Westinghouse Erin Orga
- USNC Wes Deason
- Radiant Elliott Korb



Possible FEEED Funding/Contracting Mechanism

- DOE Cost Share
 - Dependent on funding availability
 - Intended to cover costs associated with
 - NRIC/INL personnel
 - Possibly some developer costs
- Developer Funded
 - Developer covers all NRIC costs
 - Contract Type
 - CRADA
 - SPP





Westinghouse eVinciTM

Erin Orga, Program Manager eVinci External Testing April 2024



eVinci™ is a trademark or registered trademark of Westinghouse Electric Company LLC, its affiliates and/or its subsidiaries in the United States of America and may be registered in other countries throughout the world. All rights reserved. Unauthorized use is strictly prohibited. Other names may be trademarks of their respective owners. This document may contain technical data subject to the export control laws of the United States. In the event this document does contain such information, the Recipient's acceptance of this document constitutes agreement that this information in document form (or any other medium), including any attachments and exhibits hereto, shall not be exported, released or disclosed to foreign persons whether in the United States or abroad by recipient except in compliance with all U.S. export control regulations. Recipient shall include this notice with any reproduced or excerpted portion of this document, or any document derived from, based on, incorporating, using or relying on the information contained in this document.

©2024 Westinghouse Electric Company LLC. All rights reserved. Unauthorized use is strictly prohibited. Other names may be registered in other countries throughout the world. All rights reserved. Unauthorized use is strictly prohibited. Other names may be trademark or the world. All rights reserved. Unauthorized use is strictly prohibited. Other names may be trademark or the world. All rights reserved.




Westinghouse Electric Company



134

YEARS OF INNOVATION





Westinghouse established

59

other companies

He received over

360

patents for his work

Approximately
10,000
Employees


Comprised of 5
Business Units

Locations in 19
Countries

- Founded by George Westinghouse in 1886
- Responsible for some of the world's greatest advances in energy technology
- World's first commercial pressurized water reactor (PWR) in 1957 in Shippingport, Pennsylvania, U.S.



Capability



Pictured is the eVinci Electrical Demonstration Unit


Microreactor designed for safe and reliable electricity and heat generation

Technical Capabilities

- √5 MWe and ~7MWth@350F heat recovery
- ✓~13.5MWth @ >1300F heat only (future)
- ✓ Transportable for ease of installation and elimination of spent fuel storage on site
- ✓ Cost-competitive plant lifecycle
- Minimal onsite personnel
- Maturing technology, manufacturing, and regulatory readiness
- Cogeneration and load following capability




Technology





Combined Heat and Power Capability



Prospective Markets/End Uses



Remote mining operations



Industrial process heat



District heating



Remote communities



Hydrogen Generation




Marine Shipping



Critical Infrastructure Installations



Disaster relief




Research Reactors



eVinci Microreactor Deployment

Transportability Advantages




Minimizes construction cost and labor Installation to operation in less than 30 days


- ☐ Entire system delivered in four truckload size containers (40' x 14' x 14')
 - Reactor container
 - Power conversion unit
 - Instrument and controls
 - Miscellaneous support equipment
- ✓ Weights and sizes allow for deployment in remote areas (truck/rail/barge)
- ✓ Allows for rapid scaling to meet demand
- ✓ No spent fuel or waste storage on site
- ✓ Minimizes decommissioning and effort to return site to green field



Footprint


- Near 100% capacity factor versus intermittent renewable supply
- Building shields radiation
- Emergency planning zone contained within site boundary
- All construction above ground
- Site footprint: 2 acre
- Building footprint: 0.25 acre








Nuclear Test Reactor






1/5 Scaled reactor demonstration at Idaho National Lab for final data and operational information to support regulatory approval









The NTR Accelerates Commercialization

High Temp Sensors




eVinci NTR Development Locations





eVinci Accelerator













eVinci Technologies Dedicated Office

Testing, and Manufacturing Facility Etna, PA





eVinci uses 19.75% enriched Tristructural Isotropic (TRISO) fuel

Integrated Safety, from Fuel to Canister

Unlike most other reactors, eVinci microreactor is designed to operate at atmospheric pressures, eliminating risk of fission product release. The highest level of safety of fuel and radiation is maintained within many redundant layers of functional containment.

OUTER PYROLYTIC CARBON

SILICON CARBIDE

INNER PYROLYTIC
CARBON


FUEL KERNEL
(UCO, UO²)

PORUS CARBON
BUFFER




In collaboration with Urenco, Westinghouse was awarded a grant from the United Kingdom's Department for Business, Energy and Industrial Strategy (BEIS) to complete a Pre-Front End Engineering Design study for a secure and reliable supply of advanced TRISO to support a range of potential technologies in development.


October 26, 2022






Heat Pipe Technology Development














eVinci Integral Effects Test Program


<u>Testing Program – 51 Bridge St & Waltz Mill</u>





eVinci NTR

Manufacturing Development and Demonstration Progress





eVinci NTR

Manufacturing Progress

















Hardware and Prototyping Continues

Control Drum and Shutdown Rod Assemblies under active prototyping












Technology Components – Peterborough, ON office



Shut down rod and control drum component manufacturing and testing

Collaborations with Ontario Tech University






Technology Components- Burlington, ON Office








Reactor fueling and defueling component manufacturing and testing Office expansion
McMaster University, Uwaterloo, Queens U






Tooling Platform and RSS Tracks

- Flat continuous surface for tools to traverse into and out of the DOME.
- Modular platform sections for easy installation
- Stretches from INL Ramp to RSS Pedestal
- RSS Tracks are a continuation of the Tooling Platform
- Platform is secured to the DOME Floor
- RSS Tracks are bolted to the RSS Pedestal Floor on the provided bolt pattern






Tooling Platform and RSS Tracks Installed






Delivery Trolley


- Dedicated tool for transporting the NTR within the DOME
- Features two motorized Hilman Rollers, and two passively driven rollers to facilitate the motions
- Jack screws to lift and lower the NTR as needed
- Navigates on the Tooling Platform and RSS Tracks
- Includes a winch hook mechanism to attach a winch hook for NTR removal
 - Also include a cable cutting tool for cutting the control cables after the NTR is in the RTC.
- Designed to be used for both installation and removal
- Interfaces with the Transportation Skid for initial NTR Transfer.





Jack Screw Drive Motor

Delivery Trolley on Route to RSA



*Head configuration still undetermined




Closure Head Removal

Head Handling Tool

Tool Positioning System

Tooling Platform





Fueling Platform continued...

- Fuel Drum Receival:
 - Area features two dedicated spots for fuel drum pallets
 - Work area will include all hand tools required to remove the various layers of the fuel drum

 A turntable or rotating mechanism to turn the pallets for the operators to get access to every drum




Jig Crane

Fuel Drum Pallets


- Supplemental Worktable:
 - Includes all hand tools required to remove the various layers of the Fuel Drums
 - Small jib crane to assist with component removal
 - General lay-down area for components as they are being removed.

- Fuel Cartridge Hand-Off Area:
 - Dedicated space for operators to pass fully loaded fuel cartridges to the operators on the operators on the Fueling Machine
 - Potential space for in-process fuel cartridges





Fueling Machine continued...




Fueling Machine


Tool Positioning System



Fueling Tool


- Tool designed specifically to handle and load fuel into the core.
- Integrates with the Tooling Columns of the Fueling Machine
- Integrates with the fuel cartridges to secure them in place during fuel loading.
- Allows the operator to either manually push fuel into the core or make it an automated process
- Provides the operators with access to the NTR Core to manage the In-Core Thermocouples during operations.





Dovetails


Fueling Tool



Fueling Cartridge




RTC Entering through DOME Hatch





RTC at NTR




DT I&C Winch Cable

Delivery Trolley



RTC Closure - Shield Plate Install

- J-Hook for Shield Plate and Closure Head installation.
- Simple bolt on tool
- Once installed, operators can operate directly in-front (with sufficient protection)



J-Hook

Shield

Plate

University Engagements

Penn State

- Evaluating potential site locations
- Determining use case/research applications
- Considering follow on power reactors for campus heating/electricity

McMaster (Canada)

- Materials
- Potential reactor irradiation
- Research reactor product development

University of Pittsburgh

- Materials
- Modeling and simulation
- Sensors

Carnegie Mellon

- Public and international policy
- Space, materials, cyber security, Al
- MIT, Wisconsin, Texas A&M, Oregon State, + others



















@WECNuclear




Westinghouse Electric Company



wecchinanuclear

westinghousenuclear.com







Intrinsically safe nuclear power for reliable zero-carbon energy anywhere

Intrinsically Safe Micro Modular Nuclear Batteries

High Temperature Heat



Vertical Integration +
High Volumes =
Accelerated Learning Rate



Active Development Pipeline with Projects in Advanced Stages

Development / Execution / Operation / Service



Multiple Use Cases











Reactor and Fuel Factories with Rapid Deployment

Manufacture / Delivery



Supportive Regulatory Pathway

First to Market with Full-size Demos in Canada and US





Full-Stack Nuclear

Nuclear hardware and services to provide reliable energy anywhere.

CORE GROUP

Nuclear Fuels + Materials

NUCLEAR GROUP

Manufacture + Deploy

ADVANCED TECHNOLOGIES GROUP

Future Looking Product Development

INNOVATION GROUP

MMR Technology Development

2011

Founded

240+

Employees

2028

First MMR Demo









Overarching Characteristics


- FCM Fuel in geometry only possible with additive manufacturing
- Hydride moderator with regenerative cooling
- Gas coolant
- 9.9% U²³⁵ "LEU+" or 19.75% U²³⁵ HALEU
- Control drums and control rod for reactivity control




Development Philosophy

- Pylon D1 leverages extensive DOE investment and facilitations for a rapid and cost-effective technology demonstration.
- Use of MMR Fuel and systems enables leveraging of fuel irradiation and qualification and synergy with MMR design and licensing experience
- Start with low-hanging markets with straight-forward and achievable performance requirements and grow into larger and more aggressive applications











Overarching Characteristics

- FCM Fuel in geometry only possible with additive manufacturing
- Hydride moderator with regenerative cooling
- Gas coolant
- 9.9% U²³⁵ "LEU+" or 19.75% U²³⁵ HALEU
- Control drums and control rod for reactivity control












Program Overview

- Aderivative reactor is being developed to be tested at the NRIC DOME facility at Idaho National Laboratory as early as possible
 - Verify licensability and key performance, operations, safety and cost aspects.
- Reactor-focused: increase TRL of key nuclear technologies, minimize cost and schedule

Technical Performance Requirements

- Demonstration Requirements: 1 MWth @ 1000 K reactor outlet, 2.5 MW-yr core energy
- Use of 9.9% Enriched U (LEU+) (<500 kg) allows demo with **currently available fuel**
- Metal Hydride moderator






Pylon D1 1 MWth	Pylon T1 5-10MWth (1-3 MWe)
Graphite Reflector Lower-Cost	Beryllium Reflector Lower-Mass
<500 kg of 9.9% Enriched (LEU+) Available Now	19.75% Enriched (HALEU) Available Soon
Helium based Heat Removal Focus on Nuclear Demo	He-Xe Brayton Power Cycle Focus on Strong Partnership




FCM®Fuel Technology for MMRs Comprises TRISO Coated Fuel Particles Embedded inside Silicon Carbide

Fully Ceramic Microencapsulated (FCM®) Fuel

- Tri-structural isotropic (TRISO) fuel particles embedded inside an impermeable SiC matrix
- Very high fuel loading fraction owing to the unique manufacturing methodology leveraging additive techniques
- Manufacturing technology agnostic to fuel element geometry





USNC Core Technology: TRISO Fuel Embedded in Silicon Carbide - Fully Ceramic Micro-encapsulated ("FCM") Fuel

Employing the same team that made high performance TRISO fuel for the US DOE, we've developed special techniques and knowledge to steadily improve the TRISO manufacturing process. We do not rely on any other commercial or governmental entity as we own the entire vertical chain of manufacturing downstream from uranium feedstock to the fueling the final reactor core blocks

Built on TRISO

A Uranium bearing microsphere is coated with multiple special ceramic layers designed like tiny pressure vessels. These carbon and silicon carbide layers contain fission products inside and ensure mechanical and chemical stability during irradiation at high temperatures.



TRISO + Silicon Carbide (SiC) Matrix

FCM Fuel is a new approach to inherent reactor safety by providing an ultimately safe fuel. TRISO Fuel, which contains the radioactive byproducts of fission within layered carbon and Silicon Carbide (SiC) coatings. Doubling down on SiC as the main containment, these particles are then encased within a fully dense SiC matrix resulting in an extremely rugged and stable fuel with extraordinary high temperature stability.



Fuel in Any Shape

Our fuel production process leverages additive manufacturing to form the SiC matrix and as such allows for a wide variety of **fuel shapes beyond simple pins**. We can produce annular cylinders, hollow pebbles, Y-compacts and any other arbitrary shapes or particular specifications.



3D Print High-Purity Silicon Carbide

We use the same suite of manufacturing technologies to **3D print customized components** in highly pure, fully crystalline, and stoichiometric Silicon Carbide including both simple and complex parts for turbines or heat exchangers. Silicon Carbide offers extreme performance for many applications including nuclear reactors, aerospace, and defense.






136 © USNC 2023 136

Low Enriched Uranium. High Assay Low Enriched Uranium.







TRISO Manufacturing Steps: Sol-Gel, Kernel Conversion, TRISO Coating


1 Sol-Gel Module

2 Kernel Conversion Module












TRISO/FCM How Its Made






Large-Scale Binderjet Additive Manufacturing follow and Chemical Vapor Processing




Final part densification via chemical vapor infiltration (CVI)





The Combination of Binderjet and CVI facilitates 3D printing of nuclear-grade SiC in complex geometries




Additive Manufacturing Snapshot


- USNC uses binder-jet additive manufacturing for SiC and ZrC
 - High dimensional tolerance, geometry impossible by other means
- Post-print chemical vapor infiltration and/or deposition to yield parts very near as-designed


















USNC Fuel Qualification

- As defined in NUREG-2246, "Fuel Qualification for Advanced Reactors":
 - Fuel Qualification is the overall process (planning, testing, analysis, etc.) used to obtain qualified fuel.
 - Fuel is qualified when reasonable assurance exists that the fuel, <u>fabricated in accordance with its specification</u>, will perform as described in the **safety analysis**.
- Assessment framework From NUREG-2246:
 - Fuel is manufactured in accordance with a specification
 - Margin to safety limits can be demonstrated
 - Experimental data used for assessment is appropriate
 - Evaluation model is acceptable for use
- USNC submitted and NRC accepted for review our Fuel
 Qualification Methodology Topical Report

lumber: IMRDD-MMR-24-01-P leksse: 01



RESEARCH REACTOR

University of Illinois Urbana-Champaign
High-Temperature Gas-cooled Research
Reactor:
Fuel Qualification Methodology

TOPICAL REPORT

Issued by
Ultra Safe Nuclear Corporation
to
The University of Illinois Urbana-Champaign
under
USNRC Project No. 99902094

February 29, 2024



EXPORT CONTROLLED INFORMATION


TRA SAFE NUCLEAR CORPORATION PROPRIETARY INFORMATION WITHHOLD UNDER 10 CFR 2.390

1 of 107

Fuel Irradiation Plan

- Fuel qualification strategy largely unchanged, but will require irradiation of an annular pellet smaller than nominal MMR pellet
 - Enables higher enrichment and higher power density, resulting in faster accrual of required burnup
- Steady-state irradiation test: High Flux Reactor in Petten (NL)
 - Testing of USNC TRISO, FCM fuel, ODSL, and other non-fuel samples
 - Planning, experiment design, etc., currently underway
 - Testing performed on slightly smaller pellets with simplified geometry
 - Stress levels in irradiation experiment bound those in MMR
- Short-duration irradiation test: MITR
 - Testing of characteristic MMR FCM pellets beyond power densities and stress levels in MMR
 - No need for long-duration testing in MITR as nuclear heated stresses are highest at BOL
 - Reactor power will be increased incrementally to determine power and stress conditions that cause failure












© USNC 2023




TRISO Sales: NASA, private space company, and newly started collaboration with a terrestrial developer

- TRISO Commercial Sales
 - Completed successful production of nuclear fuel to NASA's Space Nuclear Power and Propulsion program.
 - UN kernel coated with buffer, iPyC, and ZrC
 - Additional production run of a similar product for a private company completed and tested in CFEET
 - Agreement and pending kickoff with a private terrestrial reactor developer
- Large-scale UCO production for MMR and Pylon ongoing
 - Produced ~30 kg UCO TRISO in recent months to optimize sol-gel, conversion, and coating parameters
 - Completion of 4.95% enriched TRISO particles for MMR fuel qualification




USNC UCO Kernel



USNC AGR-spec TRISO




UN/ZrC team with completed particles for NASA



UN/ZrC coated particle images













TRITONIC will be deployed in three phases at Framatome's existing NRC-licensed Richland, WA site:

- Phase I Manufacturing of approximately 2 MTU per year of <10% enrichment material ("LEU+")⁽¹⁾ by retooling and re-equipping an existing building on this site
- Phase II Construction of a new building on this site with the partial installation of process equipment, increasing capacity by an additional ~10 MTU per year of <10% enriched FCM Fuel
- Phase III license amendment for production of <20% enriched ("HALEU")⁽²⁾ FCM Fuel and installation of process equipment, increasing total manufacturing capacity above 20 MTU per year

Phase 1 well underway

- ✓ Purchase agreement for LEU+
- √ Equipment delivery ongoing
- ✓ License amendment submittal in Q3 2024

TRITONIC












Agenda

- Kaleidos Overview
- Radiant Company Update
- Recent Engineering Progress
- Kaleidos Development Unit (KDU) Overview
- DOME Test Campaign



Kaleidos Overview



Representative image of commercial Kaleidos unit.

- 1 MWe portable high-temperature gas-cooled microreactor
- 20 year product life, refueled 3 times
- Key safety features: TRISO fuel, helium coolant, passive cooling air jacket



Since Last Year

- Raised \$45M in April '23, \$60M total
- \$2.3M → \$8.7M in non-dilutive funding
- 29 employees → 50 employees
- Renovated and moved into 38,000 sq ft HQ
- Safety Design Strategy approved by DOE-ID
- Successful Conceptual Design Review at INL
- In Pre-Application with NRC
- Significant design and hardware development progress

Leadership Team (unchanged)



Doug Bernauer, CEO and co-founder



Bob Urberger, CTO and co-founder



Tori Baggio, COO




Ben Betzler, Head of Nuclear Eng.



Chris Hansen, Head of Mechanical Eng.



El Segundo HQ




Lease commencement - July 1, 2023




Exterior – Today



Slab upgrade – August 8, 2023



Office (23,000 sq ft) – Today Proprietary and Confidential



Move-in (shop floor) – August 21, 2023



Shop floor (15,000 sq ft) – Today



Test Stands



Air Jacket Test



Unit Cell Flow Test



Helium Circulator Loop Test



Engineering Milestones

- Zirconium Hydrides
 - Established repeatable process for hitting desired atomic ratio
- Pressure Vessel
 - Test article pressure vessel procured for passive cooldown test
- Graphite
 - Machining test of core internals complete
 - Long lead procurement for DOME test placed
- Helium Test Loop
 - Completed testing of helium circulator at operational temperatures and pressures














Kaleidos Development Unit

- Verifying performance of commercial product through real-world testing
 - Reactor core + shielding
 - Primary loop
 - Heat transfer loop



Reactor Core, Pressure Vessel and Primary Loop



NRIC and DOE Engagement

NRIC

- All FEEED deliverables submitted
- Held Conceptual Design Review
- On INL's Qualified Supplier List for design

DOE-ID

- Participation in CDR and frequent collaboration meetings
- Approval of Safety Design Strategy
- Delegation of approval for long lead bulk materials to INL



Next Steps

- Additional long lead procurements
- Phase 2 and 3 of INL NQA-1 audit
- Conceptual Safety Design Report
- Preliminary Design Safety Analysis
- Continued subsystem development and testing

Radiant remains singularly focused on the development of Kaleidos. Agile and creative problem solving will be key to maintaining our timeline for a successful test in the DOME.

